



CARDWELL L-350 700HP DRILLING RIG

DRAWWORKS:

MODEL L-350, LEBUS GROOVING 1-1/8" DRILLING LINE, MAKE UP AND BRAKEOUT, 15" DOUBLE MCKINNY HYDROMATIC, 2 ENGINE COMPOUND POWERED BY TWO CATERPILLAR 3406 RATED @ 435HP W/ QUINCY 325 AIR-COMPRESSOR.

DERRICK AND SUB STRUCTURE

LEE C MOORE (REFURBISH) 114' CRONW, RACKING BOARD, STANDPIPE, TONG COUNTER WEIGHTS, 350,000 SHL EST., BOX ON BOX 15 X 16' X 41' W/ ROTARY BEAMS AND AIR TANKS W/ 4 SETS OF STAIRS.

MUD PUMPS

2 NATIONAL K-700 A'S (REBUILT) W/ PULSATION DAMPNERS, POP OFF VALVES, AND 4" MUD VALVES, POWERED BY CAT D-379 (REBUILT)

MUD TANKS

TWO 400 BBL PITS, 7' X 10' X 40', WITH 2 CONE DESANDER, 10 CONE DESILTER, SINGLE LINEAR MOTION SHAKER, 4 MUD AGITATORS, MUD JETS AND DUMP VALVES, THREE 5" X 6" CENTRIFUGAL PUMPS W/ 60 HP ELECTRIC MOTORS AND HAND RAILS.

GENSET HOUSE

300 KW GENSET POWER BY CAT 3406 W/TWO SCREW TYPE AIR COMPRESSORS 125 CFM X 150 PSI.

ROTARY TABLE

OILWELL 17-1/2" X 44" ROTARY TABLE W/ 5-1/4" X 40' HEX KELLY W/KELLY SPINNER.

SWIVEL: BREWSTER 150 TON

TOP DOG HOUSE: 32' X 8' X 8' W/ LOCKERS, BOXES & BENCHES

FUEL TANK: 10,000 GAL. W/ DUAL FUEL PUMP AND FILTERS.

WATER TANK: 500 BBL CAP.

ACCUMULATOR: 5 STATION UNIT, CLOSING UNIT (NEW)

CHOKE MANIFOLD: 4 VALVE TWIN CHOKE @ 3000#

BOP: 11" SHAFFER DOUBLE TYPE E @ 3000#

DRILL PIPE: 9,500' OF 4" 14.40 LB W/IF CONN.

DRILL COLLARS: 20, 6-1/2" SLICK DRILL COLLARS

PIPE HANDLING TOOLS

1 SET OF BJ ROTARY TONGS, DC SLIPS, DRILL PIPE SLIPS, DRILL PIPE ELEVATORS, SAFETY CLAMPS, ROTARY TONG AND PUMP GAUGES, BOTTOM HOLE BIT SUBS, SURFACE BIT SUBS, 10-DC HANDLING TOOLS W/ 4" X-HOLE IF CONNECTIONS.

INSTRUMENTATION

SATELLITE AUTO DRILLER, MARTIN DECKER WEIGHT INDICATOR, CROWN O MATIC

DRILL LINE: 5000' OF 1-1/8" DRILL LINE

PIPE RACKS & CATWALKS: 4' X 50' CATWALK & SIX PIPE RACKS

TOOL PUSHERS OFFICE & QUARTERS / CREW QUARTERS & CHANGE HOUSE

ONE FORK LIFT: CATERPILLAR 8000# CAP. WITH EXTENDED BOOM 4 X 4 WHEEL DRIVE.